

ENERGY STAR® Program Requirements Product Specification for Connected Residential Water Heaters

Test Method to Validate Demand Response

Draft 2

October 2020

1 OVERVIEW

The following test method shall be used for determining product compliance with requirements for Demand Response (DR) functionality in the ENERGY STAR Program Requirements Product Specification for Residential Water Heaters Eligibility Criteria Version 4.0 (ENERGY STAR Specification).

2 APPLICABILITY

This test method is applicable to Residential Water Heaters designed to meet the eligibility criteria in the ENERGY STAR Specification, including the optional Connected Product Criteria found in section 4.

Note: The test method applies only to connected water heater products (CWHP) that are designed to meet the requirements of the ENERGY STAR Specification. This test method is being developed with non-ENERGY STAR water heaters with DR capabilities also in mind, and if possible, will be usable for these types of water heater as well. DOE and EPA request comment on any type of water heater with DR capabilities that cannot be tested to this test method.

3 DEFINITIONS

Unless otherwise specified, all terms used in this document are consistent with the definitions in both the ENERGY STAR Specification and in the U.S. Department of Energy (DOE) Test Procedure in Title 10 of the Code of Federal Regulations (CFR) Part 430, Appendix E to Subpart B, as of January 1, 2020 (DOE Test Procedure).

- A) Acceptable Response: The appropriate signal response from the connected water heater product (CWHP) after an operational state query is sent by the utility equivalent communication device (UECD).
- B) Appliance Communication Module: A built-in or external device that enables bi-directional communication between the CWHP and the UECD. The CWHP and appliance communication module (ACM) are included in the CWHP test boundary as specified in Figure 1 of the ENERGY STAR Specification.
- C) Load Shift Draw Pattern: The first draw cluster of the Rated Draw Pattern (i.e., draws 1 through 5 for the very-small-usage draw pattern, draws 1 through 3 for the low-usage draw pattern, draws 1 through 3 for the medium-usage draw pattern, and draws 1 through 4 for the high-usage draw pattern).
- D) Normal Mode of Operation: The operational state in which the device would be operating independent of the information exchanged through the open communication link, as set by the consumer.
- E) Operation State Query: Request from the UECD for the operation state of the CWHP.

- 41 F) Rated Draw Pattern: Draw pattern in which the CWHP was certified (i.e., either very-
42 small-usage, low-usage, medium-usage, or high-usage).
- 43 G) Rated Recovery Efficiency: Recovery efficiency in which the CWHP was certified.
- 44 H) User Interface: A means for a user to control the operation of the water heater, which may
45 be a remote and/or local user interface, such as a web-based portal, a mobile device
46 application, or an interface directly on the CWHP.
- 47 I) Utility Equivalent Communication Device: Self-contained or Personal Computer (PC)-
48 based device or devices capable of communicating with the CWHP and simulating
49 signals sent from a utility. The utility equivalent communication device or devices will be
50 controlled by the technician during the conduct of this test method, allowing the
51 technician to execute and deliver the DR requests and queries and receive necessary
52 feedback from the CWHP.
- 53 J) Acronyms:
- 54 1) ACM: Appliance Communication Module
55 2) API: Application Programming Interface
56 3) CWHP: Connected Water Heating Product
57 4) DR: Demand Response
58 5) GPM: Gallons Per Minute
59 6) ICD: Interface Control Document
60 7) LS: Load Shift
61 8) UECD: Utility Equivalent Communication Device

62 **4 TEST SETUP**

63 Unless otherwise specified, all test conditions, instrumentation, and installation requirements
64 shall be identical to sections 2, 3, and 4 of the DOE Test Procedure.

65 For solar water heaters that use grid energy as a backup heat source, all solar energy
66 connections should be disabled. The solar water heater shall then be tested according to its
67 backup heat source (e.g., if backup heating is provided by electric elements then the solar
68 water heater shall be tested as an electric resistance water heater and if backup heating is
69 provided by a gas burner then the solar water heater shall be tested as a gas-fired water
70 heater).


71 **4.1 Connected Water Heater Product (CWHP) System Setup**

72 The ACM and UECD shall be set up in accordance with manufacturer instructions in the
73 open standard protocol, ICD, and/or API. The communication devices must be set up as
74 follows:

- 75 A) Establish the connection between the ACM and the UECD via wired or wireless
76 connection depending on the ACM's capability. If both a wired and wireless connection
77 are available, connection between the ACM and UECD shall be through the wireless
78 connection.
- 79 B) Ensure that the ACM is connected properly and can both receive and send data to the
80 UECD, in accordance with manufacturer instructions.


81 For CWHP designed to be used with a mixing valve (e.g., the CWHP raises the temperature
82 of water in the tank above the temperature of the water after all thermostats are satisfied at
83 the user setpoint under normal operation, as specified in section 5.2.2 of the DOE Test
84 Procedure, and that do not have a self-contained mixing valve), a mixing valve shall be

85 installed according to the water heater and mixing valve manufacturer's instructions and to
86 Figure 1 or Figure 2. If permitted by the water heater and mixing valve manufacturer's
87 instructions, the mixing valve may be installed in the outlet line where the elbow closest to
88 the outlet is located. If there are no installation instructions for the mixing valve in the water
89 heater or mixing valve manufacturer's instructions, then the mixing valve shall be installed
90 on the outlet line, as shown in Figure 1 or Figure 2, and the cold water shall be supplied from
91 the inlet line where a junction is installed after the location where T_{IN} is measured. The outlet
92 temperature, liquid flow rate, and/or mass measuring instrumentation, if installed on the
93 outlet side of the CWHP, shall be installed after the mixing valve.



94

95 **Figure 1:** Mixing Valve location on a CWHP with top inlet and outlet connections



96

97 **Figure 2:** Mixing Valve location on a CWHP with side inlet and outlet connections

98 **Note:** A commenter suggested adding an inlet bypass loop to the test setup similar to AHRI's
 99 "Guideline for Testing Uniform Energy Factor for Electric, Gas, and Oil-Fired Residential
 100 and Residential-Duty Commercial Water Heaters." EPA and DOE have tentatively
 101 determined that this addition is not necessary and that while inlet bypass loops are commonly
 102 used by test labs to condition inlet water it is not required to run the test.

103 DOE and EPA request comment on the mixing valve installation instructions. Specifically,
 104 where should the inlet line tee be located and what default instructions are necessary when
 105 instruction is not provided in the water heater or mixing valve manufacturer's instructions?

106 5 WATER HEATER PREPARATION

107 This section does not need to be performed to complete the CWHP Initialization (section
 108 6.1), User Interface (section 6.2), Consumer Override (section 6.3), and Loss of Connectivity
 109 (section 6.4) tests.

110 Prior to the Load Shift (section 6.5.1) and Emergency Curtailment and Grid Emergency
 111 (section 6.5.2) tests, perform the procedures found in section 5.1 and 5.2 of the DOE Test
 112 Procedure. These include the operational mode selection, determination of storage tank
 113 volume, V_{st} , setting the outlet discharge temperature, power input determination, and a soak-
 114 in period.

115 When setting the outlet discharge temperature, first use the settings as shipped from the
 116 manufacturer. If the requirements in section 5.2.2 of the DOE Test Procedure are not met,
 117 then adjust the temperature controller and repeat the procedures for setting the outlet
 118 discharge temperature.

119 If the DOE Test Procedure was performed prior to this test method and electricity and/or
120 fossil fuel supply have not been removed from the CWHP, then the soak-in period from
121 section 5.2.4 of the DOE Test Procedure does not need to be conducted.

122 **Note:** A commenter stated that the outlet water temperature used in the DOE Test Procedure
123 and this test method may not align with the settings required in California’s Title 24 Joint
124 Appendix 13 (JA 13), which states that the water heater setting is “as shipped.” It is DOE and
125 EPA’s understanding that most models are shipped set to deliver water between 120°F and
126 125°F, which would be within the outlet water temperature tolerance required in the DOE
127 Test Procedure and this test method. EPA and DOE adjusted the language in section 5 to
128 address this but acknowledge that if the criteria in section 5.2 of the DOE Test Procedure
129 cannot be met with the setpoint “as shipped” then then setpoint will need to be set according
130 to the DOE Test Procedure. This change allows for CWHP to be compared in a consistent
131 manner and helps to align the ENERGY STAR Specification and test method requirements
132 with JA 13.

133 EPA and DOE note that the soak-in period from section 5.2.4 of the DOE Test Procedure is
134 required to be greater than or equal to 12 hours. Therefore, if desired, the soak-in period
135 could be longer than 12 hours.

136 **6 DEMAND RESPONSE TESTS**

137 In sections 6.3 through 6.5 test instructions are provided in table form where each row is a
138 distinct step. DR requests are sent with a start time and duration. Start times can be either
139 “Immediately” (i.e., as soon as the request is received by the CWHP) or at a certain time after
140 the request is received by the CWHP. Durations are stated as either “Maximum” or some
141 other duration (e.g., 4 hours). For all tests except the Loss of Connectivity test in section 6.4,
142 a “Maximum” duration in the context of this test method means first, that the DR request
143 does not end, and second, if the CWHP is incapable of receiving a DR request that does not
144 end, then the DR request will last at least 4 hours.

145 **6.1 CWHP Initialization**

146 Verify that the CWHP communicates using an open standard as defined in section 4.D.a of
147 the ENERGY STAR Specification.

148 **6.2 User Interface**

149 Verify that the manufacturer literature supplied with the CWHP and/or ACM includes
150 instructions for the user to override DR requests.

151 **Note:** A commenter recommended aligning the user interface requirements with those under
152 consideration in JA 13, including: product connectivity status, DR event status, active control
153 strategy (if any), demand management mode, time-of-use schedule (if applicable), and
154 confirmation of setting changes. If user interface changes are proposed in the Final Draft of
155 the ENERGY STAR Specification, then this test method will be updated to account for those
156 changes.

157 **6.3 Consumer Override**

158 The test steps described in Table 1 shall be performed for the General Curtailment request to
 159 verify the consumer override requirement of section 4.D.b of the ENERGY STAR
 160 Specification.

161 All communications between the UECD and CWHP must be logged. If any logged
 162 communications do not match the acceptable responses, then the CWHP fails.

163 **Table 1: Consumer Override Verification Test Steps**

Step	UECD	CWHP
1	Send a Return to Normal Operation request.	
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3	Send a General Curtailment request. Start Time = Immediately Duration = Maximum	The CWHP must acknowledge the request.
4	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
5	Initiate consumer override either through the local or remote user interface.	
6	Send an Operational State query.	Acceptable responses include: “Idle Opted Out” or “Running Opted Out”
7	Send a General Curtailment request. Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
8	Send an Operational State query.	Acceptable responses include: “Idle Opted Out” or “Running Opted Out”
9	End consumer override either through the local or remote user interface.	
10	Send a General Curtailment request.	CWHP must acknowledge the request.

Step	UECD	CWHP
	Start Time = Shortest possible duration allowing for time to complete Step 11 Duration = Maximum	
11	Initiate consumer override either through the local or remote user interface.	
12		Wait for Start Time from Step 10.
13	Send an Operational State query.	Acceptable responses include: “Idle Opted Out” or “Running Opted Out”
14	End consumer override either through the local or remote user interface.	
15	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”

164 **Note:** A commenter suggested testing that the Consumer Override expires after a set time
165 period. EPA and DOE have tentatively determined that waiting for this set time period will
166 unduly increase the test time and burden, as the CWHP will be sitting on the test stand not
167 running for an extended period of time.

168 A commenter suggesting adding a calculation to determine that the CWHP returns to Normal
169 Operation when the Consumer Override is initiated. EPA and DOE have tentatively
170 determined that a calculation in the Consumer Override test is unnecessary as the CWHP
171 response to DR requests is checked in the Load Shift and Emergency Curtailment and Grid
172 Emergency tests found in sections 6.5.1 and 6.5.2, respectively.

173 **6.4 Loss of Connectivity**

174 The test steps described in Table 2 shall be performed to verify the loss of connectivity
175 requirement of section 4.D.c of the ENERGY STAR Specification.

176 If unable to automatically verify operational state when connectivity is removed, manually
177 verify operational state on the local user interface.

178 All communications between the UECD and CWHP must be logged. If any logged
179 communications do not match the acceptable responses, then the CWHP fails.

180 **Table 2: Loss of Connectivity Verification Test Steps**

Step	UECD	CWHP
1	Send a Return to Normal Operation request.	

Step	UECD	CWHP
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3	For CWHP’s capable of receiving DR requests without a set duration or end time, send a General Curtailment request. Otherwise, skip to step 11. Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
4	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
5		Remove connectivity and wait for the criteria described in section 4.D.c of the ENERGY STAR Specification to occur.
6		Wait for the time specified in section 4.D.c.ii of the ENERGY STAR Specification.
7		Re-establish connectivity and allow unit to perform any connection operations.
8	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
9	Send a Return to Normal Operation request.	
10	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
11	For CWHP’s capable of receiving DR requests with a set duration or end time, send a General Curtailment request. Otherwise, end test. Start Time = Immediately Duration = 4 hours	The CWHP must acknowledge the request.
12	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
13		Remove connectivity and wait for the criteria described in section 4.D.c of the ENERGY STAR Specification to occur.

Step	UECD	CWHP
14		Re-establish connectivity and allow unit to perform any connection operations.
15	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
16	Send a Return to Normal Operation request.	
17	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”

181 **6.5 Demand Response Requests and Responses**

182 This section verifies the DR Requests and Responses of the CWHP as required by section
183 4.D.e of the ENERGY STAR Specification.

184 All communications between the UECD and CWHP must be logged. If any logged
185 communications do not match the acceptable responses, then the CWHP fails.

186 Prior to the Load Shift (section 6.5.1) and Emergency Curtailment and Grid Emergency
187 (section 6.5.2) tests perform the water heater preparation procedures from section 5.

188 Table 3 uses the Rated Draw Pattern to provide the flow rate used during the Load Shift and
189 the Emergency Curtailment and Grid Emergency tests. The CWHP’s Rated Draw Pattern is
190 also used to determine the Load Shift Draw Pattern as described in section 3.

191 **Table 3: Flow Rate Used in the Load Shift and Emergency Curtailment and Grid**
192 **Emergency Tests**

Rated Draw Pattern	Flow Rate
Very-Small-Usage	1.0 gpm ± 0.1 gpm
Low-Usage	1.7 gpm ± 0.1 gpm
Medium-Usage	1.7 gpm ± 0.1 gpm
High-Usage	3.0 gpm ± 0.25 gpm

193 During the Load Shift and Emergency Curtailment and Grid Emergency tests described in
194 sections 6.5.1 and 6.5.2, respectively, instructions are given to allow the CWHP to settle. To
195 “settle” in this test method is to allow the CWHP to operate without drawing water or
196 recovering for 10 minutes after a cut-out. If a cut-in occurs before 10 minutes have elapsed
197 after cut-out, then the recovery should be allowed to continue until cut-out, at which time the
198 10-minute settling period will begin again, and, if necessary, repeat until a full 10-minute
199 settling period is performed.

200 **6.5.1 Load Shift**

201 The test steps described in Table 4 shall be performed to verify the requirements for the
202 General Curtailment and either the Basic or Advanced Load Up requests from section 4.D.f
203 of the ENERGY STAR Specification. The Load Shift test includes performing the Load Shift
204 Draw Pattern with the CWHP in the Normal Mode of Operation, a load up (either a Basic or

205 Advanced Load Up), and then performing the Load Shift Draw Pattern with the CWHP
 206 operating under a General Curtailment request. Only one load up request is required (i.e., if
 207 the Basic Load Up is tested then verification of the Advanced Load Up is not required, and
 208 vice versa). Several steps in Table 4 use the flow rate that is determined using Table 3.

209 Record the mean tank temperature and energy usage at the beginning of the test and every 5
 210 seconds afterward.

211

Table 4: Load Shift Test Steps

Step	UECD	CWHP
If verifying the Advanced Load Up request, first enable Advanced Load Up operation.		
1	Send a Return to Normal Operation request.	
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3	Send a Device Type query.	CWHP must respond with Device Type.
4		If CWHP is undergoing a recovery, wait until cut-out and allow the CWHP to settle. If a recovery is not occurring, draw off water at the flow rate as determined using Table 3 until a cut-in occurs. Wait until cut-out and allow CWHP to settle.
Verification of Normal Mode of Operation		
5*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
6		Perform the Load Shift Draw Pattern. If the Basic Load Up request will be verified and a recovery initiates during the first draw of the Load Shift Draw Pattern, record the volume drawn at the initiation of the recovery.
7		Wait until 4 hours from the start of step 5 have elapsed.
8*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total	CWHP must respond to all queries.

Step	UECD	CWHP
	Energy Storage Capacity queries.	
9		<p>If a recovery is occurring, wait until cut-out and allow the CWHP to settle.</p> <p>If a recovery is not occurring, draw off water at the flow rate as determined using Table 3 until a cut-in occurs. Wait until cut-out and allow CWHP to settle.</p>
10*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
Verification of the Basic Load Up or Advanced Load Up Request		
11		<p>If a recovery initiated in the first draw of step 6, skip to step 12.</p> <p>If a recovery did not initiate in the first draw of step 6, draw off water at the flow rate as determined using Table 3. Stop drawing water when a cut-in occurs and wait for the CWHP to settle after cut-out.</p>
12		<p>Draw off water at the flow rate as determined using Table 3. If a recovery initiated in the first draw of step 6, stop drawing water when 2 gallons less than the volume drawn in step 6 have been drawn. If a recovery did not initiate in the first draw of step 6, stop drawing water when 2 gallons less than the volume drawn in step 11 have been drawn. If a cut-in occurs at any time before step 14, wait for the CWHP to settle after cut-out, and restart this step. After a restart of this step (only when necessary) draw off 1 gallon less than the volume drawn immediately before cut-in during the previous iteration until a volume of water is drawn off and no cut-in occurs.</p>
13*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.

Step	UECD	CWHP
14	Send either a Basic Load Up or Advanced Load up request. Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
15*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
16		If a cut-in does not occur within 5 minutes of sending the Basic Load Up or Advanced Load Up request, then the CWHP fails.
17*	If there was a delayed cut-in as described in step 16, perform this step. Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
18	Send an Operational State query.	Acceptable responses include: "Running Heightened Grid"
19		Wait for the CWHP to settle after cut-out.
Verification of the General Curtailment Request		
20*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
21	Send a General Curtailment request. Start Time = Immediately Duration = Maximum. If the CWHP cannot accommodate a request without an end time, then	CWHP must acknowledge the request.

Step	UECD	CWHP
	the duration will be set to greater than or equal to 4 hours.	
22	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
23		Perform the Load Shift Draw Pattern.
24		Wait until 4 hours from the start of step 20 have elapsed.
25*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
26	Send a Return to Normal Operation request.	
27	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
28*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
29		Wait for the CWHP to settle after cut-out. If a recovery does not occur after 10 minutes, move on to the next step.
30*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
* Calculate the energy content of the stored hot water in the CWHP as described in section 7.1.1.1.		

212 Determine the total energy consumed during the normal operation, Basic Load Up or
213 Advanced Load Up, and General Curtailment events:

214 Q_{Normal} = total energy consumption, including auxiliary energy use, between the start of step 5
215 and the end of step 8, Btu (Wh).

216 $Q_{\text{Basic Load Up}}$ = if applicable, total energy consumption, including auxiliary energy use,
217 between step 13 and the end of step 20, Btu (Wh).

218 $Q_{\text{Advanced Load Up}}$ = if applicable, total energy consumption, including auxiliary energy use,
219 between step 13 and the end of step 20, Btu (Wh).

220 $Q_{\text{General Curtailment}}$ = total energy consumption, including auxiliary energy use, between the start
221 of step 20 and the end of step 25, Btu (Wh).

222 Q_{Reheat} = total energy consumption, including auxiliary energy use, between the start of step
223 25 to the end of step 30, Btu (Wh).

224 Verify that: $Q_{\text{Normal}} > Q_{\text{General Curtailment}}$

225 Verify through electrical and/or fossil fuel supply measurements that the CWHP began
226 heating water after the Basic Load Up or Advanced Load Up request was sent in step 14 and
227 at or before the time limit described in step 16.

228 **Note:** EPA and DOE are proposing a Load Shift test to verify functionality of CWHP in the
229 DR modes that are likely to be used the most (i.e., Basic or Advanced Load Up and General
230 Curtailment) with a test that is intended to be representative of actual use in the field, while
231 also minimizing test burden. A separate test for each DR request is not being proposed to
232 further reduce test burden.

233 During the Load Shift test, a 4-hour General Curtailment evaluation period is being proposed.
234 This 4-hour General Curtailment period is being compared to a 4-hour period of operation in
235 Normal Mode to determine whether the CWHP operates as required in General Curtailment
236 mode. In Draft 1 of this test method, EPA and DOE requested feedback on whether a 4-hour
237 General Curtailment period adequately represents the typical use of CWHP. Commenters
238 generally supported the 4-hour General Curtailment period and one commenter asked for
239 clarification on why the 4-hour period was chosen. The 4-hour period was discussed and
240 generally accepted as a reasonable length during in-person meetings, it corresponds to the
241 peak time range (i.e., 5:00 pm to 9:00 pm) which was evaluated to determine the Basic and
242 Advanced Load Shift values, and when examining the available test data for heat pump water
243 heaters, the data showed that the water heater could fully recover from the first draw cluster
244 of the DOE Test Procedure within a 4-hour period. For these reasons, the 4-hour General
245 Curtailment period was proposed.

246 The energy used values, which are used to determine whether the CWHP meets the minimum
247 Basic or Advanced Load Shift specified in the ENERGY STAR Specification section 4.D.d,
248 are currently found immediately at the end of the 4-hour period regardless of whether a
249 recovery is occurring. In other words, if a recovery is occurring at the end of the 4-hour
250 period, the energy used after hour 4 is not currently used in the energy use calculations.
251 Section 4.A of the ENERGY STAR Specification states that, "A load shift operation moves
252 energy that would have been used by the CWHP under normal operating conditions within an
253 interval to outside that interval." Therefore, the intervals under normal operation and General
254 Curtailment should be the same and will not be if the intervals can be extended past hour 4.

255 In Draft 1 of this test method, EPA and DOE requested comment on whether the CWHP
256 would operate differently when the end time of the General Curtailment period is known in
257 advance, as opposed to when the end time is unspecified (e.g., would a unit delay a recovery

258 until after General Curtailment if it knows the end of the period is near). In response, one
259 commenter stated that the CWHP would not operate differently and another commenter
260 stated that depending on the complexity of the control system, knowing the end time of the
261 event could impact the behaviour of the CWHP. EPA and DOE have tentatively determined
262 to send the General Curtailment request with no end time, if possible, for the CWHP being
263 tested. The CWHP will likely not delay a recovery that would occur near the end of the 4-
264 hour period if it is not aware that the General Curtailment will soon be ending.

265 DOE and EPA have proposed the addition of a reheat period after the end of the General
266 Curtailment period to help determine whether a CWHP will immediately initiate a recovery.
267 DOE and EPA request comment on the usefulness of this information and how it can be
268 incorporated into this test method and the ENERGY STAR Specification. This reheat period
269 does not affect the load shift calculations found in section 7.1.3.

270 In Draft 1 of the test method no draw was required prior to sending the Advanced Load Up
271 request, therefore the Draft 1 test method captured the energy use to bring the CWHP from
272 the normal operation setpoint energy state to a higher energy state. In this document a draw is
273 required prior to the Advanced Load Up and captures the energy use to bring the CWHP from
274 a depleted energy state to a higher energy state. This draw is the same as the draw required
275 when verifying the Basic Load Up. During the testing of an 80-gallon high-usage CWHP, the
276 Basic Load Shift was observed to be greater than the Advanced Load Shift. The Advanced
277 Load Shift should be higher than the Basic Load Shift for the same CWHP, therefore, DOE
278 and EPA have proposed adding a draw prior to the Advanced Load Up request to capture the
279 energy use to bring the CWHP from a depleted energy state to the normal operation setpoint
280 energy state. The energy use to bring the CWHP from the normal operation energy state to
281 the higher energy state is still being captured. DOE and EPA request comment on this
282 revision.

283 DOE and EPA observed once that a CWHP did not immediately cut-in after receiving a Basic
284 Load Up request. The CWHP cut-in about 3 minutes after the Basic Load Up request was
285 sent. Prior to the Basic Load Up request being sent a draw was performed to get the CWHP
286 into a depleted energy state. DOE and EPA believe this could have occurred due to internal
287 tank stratification and that some time may be required for some CWHP to recognize that they
288 are in a depleted energy state and capable of loading up. Therefore, DOE and EPA have
289 proposed to allow the CWHP 5 minutes to initiate a cut-in after a Basic or Advanced Load
290 Up request is sent. If a cut-in does not occur within 5 minutes of sending the Basic or
291 Advanced Load Up request, then the CWHP would fail. DOE and EPA request comment on
292 whether 5 minutes is an appropriate length of time to wait for a cut-in after a Basic or
293 Advanced Load Up request is sent.

294 DOE and EPA have removed language indicating that electric resistance elements cannot turn
295 on during a General Curtailment event. Per the revised ENERGY STAR Specification
296 language, the water heater shall avoid use of electric resistance elements during and
297 immediately after the event, but electric resistance elements can turn on if user needs cannot
298 be met.

299 **6.5.2 Emergency Curtailment and Grid Emergency**

300 Perform the test steps described in Table 5 to verify the Emergency Curtailment and Grid
301 Emergency requirements from section 4.D.f of the ENERGY STAR Specification.

302 For CWHP that use heat pump technology along with resistance elements, if the resistance
 303 elements turn on at any point during an Emergency Curtailment event, then the CWHP fails.
 304 For CWHP that use only resistance heating elements, if any element but the top element turn
 305 on at any point during an Emergency Curtailment event, then the CWHP fails. For all CWHP,
 306 if any energy is used to heat water during a Grid Emergency event, then the CWHP fails.

307 Record the energy usage at the beginning of the test and every 5 seconds afterward.
 308 Measurements of the outlet temperatures shall be made 5 seconds after the draw is initiated
 309 and at every subsequent 3-second interval throughout the duration of each draw. Use Table 3
 310 to determine the flow rate used in the Emergency Curtailment and Grid Emergency
 311 Verification Test.

312 **Table 5: Emergency Curtailment and Grid Emergency Verification Test Steps**

Step	UECD	CWHP
1	Send a Return to Normal Operation request.	
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3		If CWHP is undergoing a recovery, wait for the CWHP to settle after cut-out.
4*	Send Power/Demand and Current Available Energy Storage Capacity queries.	CWHP must respond to all queries.
5	Send an Emergency Curtailment request Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
6	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
7		Draw off water at the flow rate as determined using Table 3. When the delivery temperature reaches 80 °F (26.7 °C) continue with the next step.
8	Send a Grid Emergency request Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
9*	Send Power/Demand and Current Available Energy Storage Capacity queries.	CWHP must respond to all queries.

Step	UECD	CWHP
10		Stop drawing water when delivery temperature drops below 60 °F (37.8 °C).
11	Send a Return to Normal Operation request.	
12	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
* Calculate the energy content of the stored hot water in the CWHP as described in section 6.6.3.		

313 If testing a CWHP that uses heat pump and electric resistance elements, verify through
314 electrical supply measurements that the elements do not turn on between steps 5 and 7.

315 Verify through electrical and/or fossil fuel supply measurements that energy was not used to
316 heat water between steps 8 and 10.

317 **6.6 DR Information and Messaging**

318 Sections 6.6.1 to 6.6.5 verify the appropriate responses required in section 4.D.e of the
319 ENERGY STAR Specification.

320 **6.6.1 Device Type**

321 Verify that the device type recorded in step 3 of the Load Shift test described in Table 4 of
322 section 6.5.1 is the correct device type.

323 **6.6.2 Operational State**

324 The Operational State messaging is verified in sections 6.3 through 6.5.

325 **6.6.3 Current Available Energy Storage Capacity**

326 Verify that a response is being received from the Current Available Energy Storage Capacity
327 queries at each of the indicated steps in Table 4 of section 6.5.1 for the Load Shift test (i.e.,
328 steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and 30) and Table 5 of section 6.5.2 for the Emergency
329 Curtailment and Grid Emergency test (i.e., steps 4 and 9).

330 **6.6.4 Current Total Energy Storage Capacity**

331 Verify that a response is being received from the Current Total Energy Storage Capacity
332 queries at each of the indicated steps in Table 4 of section 6.5.1 for the Load Shift test (i.e.,
333 steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and 30) and Table 5 of section 6.5.2 for the Emergency
334 Curtailment and Grid Emergency test (i.e., steps 4 and 9).

335 **6.6.5 Power/Demand (Instantaneous)**

336 Verify that a response is being received from the Power/Demand (Instantaneous) queries at
337 each of the indicated steps in Table 4 of section 6.5.1 for the Load Shift test (i.e., steps 5, 8,

338 10, 13, 15, 17, 20, 25, 28, and 30) and Table 5 of section 6.5.2 for the Emergency
339 Curtailment and Grid Emergency test (i.e., steps 4 and 9).

340 Verify that the Power/Demand (Instantaneous) CWHP responses in steps 5, 10, 13, 20, and
341 30 in the Load Shift test from section 6.5.1 and steps 4 and 9 for the Emergency Curtailment
342 and Grid Emergency test from section 6.5.2 were less than the CWHP responses in step 15
343 (or step 17, if performed).

344 **7 CALCULATIONS**

345 **7.1.1 Accuracy of Current Available Energy Storage Capacity**

346 *7.1.1.1 Energy Content of the Stored Water*

347 Calculate the energy content of the stored water in the CWHP at each of the indicated steps in
348 Table 4 of section 6.5.1 for the Load Shift test (i.e., steps 5, 8, 10, 13, 15, 17, 20, 25, 28 and
349 30).

$$350 \quad E_{Step} = V_{st} \rho C_p \bar{T}_{Step}$$

351 Where,

352 E_{Step} = stored energy content of the CWHP during a specific step, Btu (Wh).

353 V_{st} = stored volume of the CWHP as found in section 5, gal (L).

354 ρ = density of the stored water at \bar{T}_{Step} , lb/gal (kg/L).

355 C_p = specific heat of stored water at \bar{T}_{Step} , Btu/(lb °F) (kJ/(kg °C)).

356 \bar{T}_{Step} = mean tank temperature during a specific step, °F (°C).

357 *7.1.1.2 Energy Content of the Stored Water after Cut-out during Normal Operation*

358 Calculate the average energy content of the CWHP when the mean tank temperature reaches
359 the maximum mean tank temperature after cut-out during normal operation, $\bar{E}_{Setpoint}$, by
360 averaging the calculated energy content of the CWHP at steps 5 and 10 from the Load Shift
361 test in Table 4. If the Basic Load Up request was verified then also include the calculated
362 energy content at step 20 the calculation (i.e., average of 3 different energy content
363 measurements if the Basic Load Up request was verified or 2 different energy content
364 measurements if the Advanced Load Up request was verified).

365 *7.1.1.3 Current Available Energy Storage Capacity*

366 Calculate the Current Available Energy Storage Capacity at each of the indicated steps in
367 Table 4 of section 6.5.1 for the Load Shift test (i.e., steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and
368 30). Note, there are 10 Current Available Energy Storage Capacity values.

$$369 \quad AE_{C,Step} = \frac{100 (\bar{E}_{Setpoint} - E_{Step})}{RE_{Rated}}$$

370 Where,

371 $AE_{C, Step}$ = calculated Current Available Energy Storage Capacity for a specific step, Btu
372 (Wh).

373 RE_{Rated} = rated recovery efficiency.

374 7.1.1.4 Root-Mean-Square Difference (RMSD)

375 Calculate the RMSD between the calculated Current Available Energy Storage Capacity and
376 the recorded Current Available Storage Energy Capacity values which were supplied by the
377 CWHP during the Load Shift test from section 6.5.1.

$$378 \quad RMSD_{AE} = \sqrt{\frac{\sum(AE_{C, Step} - AE_{R, Step})^2}{N}}$$

379 Where,

380 $RMSD_{AE}$ = root-mean-square-difference between the calculated Current Available Energy
381 Storage Capacity and the recorded Current Available Energy Storage Capacity, Btu (Wh).

382 $AE_{R, Step}$ = recorded Current Available Energy Storage Capacity supplied by the CWHP for a
383 specific step, as stated in section 7.1.1.3, Btu (Wh).

384 N = number of times the Current Available Energy Storage Capacity is measured during the
385 Load Shift test (i.e., 10).

386 7.1.2 Accuracy of Current Total Energy Storage Capacity

387 These calculations are optional and only apply to CWHP capable of receiving and responding
388 to Current Total Energy Storage Capacity requests.

389 7.1.2.1 Energy Content of the Stored Water at High Energy State

390 Determine the maximum mean tank temperature recorded between steps 10 and 21 of the
391 Load Shift test found in Table 4 of section 6.5.1, \bar{T}_{High} , °F (°C).

392 Calculate the energy content of the stored water in the CWHP at the high energy state.

$$393 \quad E_{High} = V_{st} \rho C_p \bar{T}_{High}$$

394 Where,

395 E_{High} = stored energy content of the CWHP at the high energy state, Btu (Wh).

396 V_{st} = stored volume of the CWHP as found in section 5, gal (L).

397 ρ = density of the stored water at \bar{T}_{Low} , lb/gal (kg/L).

398 C_p = specific heat of stored water at \bar{T}_{Low} , Btu/(lb °F) (kJ/(kg °C)).

399

400 7.1.2.2 *Energy Content of the Stored Water at Low Energy State*

401 Determine the minimum mean tank temperature recorded between steps 21 and 24 of the
402 Load Shift test found in Table 4 of section 6.5.1, \bar{T}_{Low} , °F (°C).

403 Calculate the energy content of the stored water in the CWHP at the low energy state.

404
$$E_{Low} = V_{st} \rho C_p \bar{T}_{Low}$$

405 Where,

406 E_{Low} = stored energy content of the CWHP at the low energy state, Btu (Wh).

407 7.1.2.3 *Current Total Energy Storage Capacity*

408 Calculate the Current Total Energy Storage Capacity.

409
$$TE_C = \frac{100 (E_{High} - E_{Low})}{RE_{Rated}}$$

410 Where,

411 TE_C = calculated Current Total Energy Storage Capacity, Btu (Wh).

412 RE_{Rated} = rated recovery efficiency.

413 7.1.2.4 *Root-Mean-Square Difference (RMSD)*

414 Calculate the RMSD between the calculated Current Total Energy Storage Capacity and the
415 recorded Current Total Storage Energy Capacity values which were supplied by the CWHP
416 during the Load Shift test from section 6.5.1 (i.e., steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and
417 30). Note, there are 10 Current Total Energy Storage Capacity values.

418
$$RMSD_{TE} = \sqrt{\frac{\sum (TE_C - TE_{R,Step})^2}{N}}$$

419 Where,

420 $RMSD_{TE}$ = root-mean-square-difference between the calculated Current Total Energy
421 Storage Capacity and the recorded Current Total Energy Storage Capacity, Btu (Wh).

422 $TE_{R,Step}$ = recorded Current Total Energy Storage Capacity supplied by the CWHP for a
423 specific step, Btu (Wh).

424 N = number of times the Current Total Energy Storage Capacity is measured during the Load
425 Shift test (i.e., 10).

426 **Note:** A commenter requested that optional procedures and calculations be added to
427 determine the accuracy of the Current Total Energy Storage Capacity responses. DOE and
428 EPA request comment on whether the inclusion of these procedures and calculations should

429 be maintained in the Final Draft of this test method. Further, comments are requested on
430 whether the accuracy of the Current Total Energy Storage Capacity is adequately captured.

431 **7.1.3 Load Shift**

432 If the Basic Load Up request was verified during the Load Shift test, verify that the CWHP
433 meets the requirements of a Basic Load Shift.

$$434 \quad Q_{Basic\ Load\ Up} + (Q_{Normal} - Q_{General\ Curtailment}) \geq Basic\ Load\ Shift$$

435 Where,

436 Q_{Normal} = as defined in section 6.5.1.

437 $Q_{Basic\ Load\ Up}$ = as defined in section 6.5.1.

438 $Q_{General\ Curtailment}$ = as defined in section 6.5.1.

439 Basic Load Shift = as defined in section 4.D.d.i of the ENERGY STAR Specification.

440 If the Advanced Load Up request was verified during the Load Shift test, verify that the
441 CWHP meets the requirements of an Advanced Load Shift.

$$442 \quad Q_{Advanced\ Load\ Up} + (Q_{Normal} - Q_{General\ Curtailment}) \geq Advanced\ Load\ Shift$$

443 $Q_{Advanced\ Load\ Up}$ = as defined in section 6.5.1.

444 Advanced Load Shift = as defined in section 4.D.d.ii of the ENERGY STAR Specification.

445 **Note:** A commenter requested that load shift test data be published. DOE and EPA have
446 tentatively determined not to publish actual test data but will comment on the testing and
447 results. Testing started with an amended version the Draft 1 test method with updates that
448 were recommended by commenters. As the test lab worked through the test method, areas
449 that required further clarification or direction were identified and amended. The amended test
450 method was then run. A 50-gallon medium-usage and an 80-gallon high-usage CWHP were
451 tested to verify both the Basic and Advanced Load Up requests. In all tests, the measured
452 load shift was greater than the required load shift from the ENERGY STAR Specification.

453 **8 REFERENCES**

454 A) 10 CFR Part 430, Subpart E, Appendix B. Uniform Test Method for Measuring the
455 Energy Consumption of Water Heaters (as of January 1, 2020).

456 B) ENERGY STAR Program Requirements Product Specification for Residential Water
457 Heaters Version 4.0 (Rev. Jan-2020).