

ENERGY STAR® Program Requirements Product Specification for Connected Residential Water Heaters

Test Method to Validate Demand Response

Final Draft

February 2021

1 OVERVIEW

The following test method shall be used for determining product compliance with requirements for Demand Response (DR) functionality in the ENERGY STAR Program Requirements Product Specification for Residential Water Heaters Eligibility Criteria Version 4.0 (ENERGY STAR Specification).

Note: In the Version 4.0 of the ENERGY STAR Specification, EPA has updated the connected product criteria in section 4 to explicitly state that the consumer override be limited to 72 hours without additional user input, that a CWHP capable of storing and operating with a time of use schedule may continue to operate on that schedule during a loss of connectivity event, and add demand response message mapping for the operational states presented in section 4.D.d. This test method refers to the sections as they are presented within the Final Draft of version 4.0 of the ENERGY STAR Specification.

2 APPLICABILITY

This test method is applicable to Residential Water Heaters designed to meet the eligibility criteria in the ENERGY STAR Specification, including the optional Connected Product Criteria found in section 4.

3 DEFINITIONS

Unless otherwise specified, all terms used in this document are consistent with the definitions in both the ENERGY STAR Specification and in the U.S. Department of Energy (DOE) Test Procedure in Title 10 of the Code of Federal Regulations (CFR) Part 430, Appendix E to Subpart B, as of January 1, 2020 (DOE Test Procedure).

- A) Acceptable Response: The appropriate signal response from the connected water heater product (CWHP) after an operational state query is sent by the utility equivalent communication device (UECD).
- B) Appliance Communication Module: A built-in or external device that enables bi-directional communication between the CWHP and the UECD. The CWHP and appliance communication module (ACM) are included in the CWHP test boundary as specified in Figure 1 of the ENERGY STAR Specification.
- C) Load Shift Draw Pattern: The first draw cluster of the Rated Draw Pattern (i.e., draws 1 through 5 for the very-small-usage draw pattern, draws 1 through 3 for the low-usage draw pattern, draws 1 through 3 for the medium-usage draw pattern, and draws 1 through 4 for the high-usage draw pattern).
- D) Normal Mode of Operation: The operational state in which the device would be operating independent of the information exchanged through the open communication link, as set by the consumer.
- E) Operation State Query: Request from the UECD for the operation state of the CWHP.

- 42 F) Rated Draw Pattern: Draw pattern in which the CWHP was certified (i.e., either very-
43 small-usage, low-usage, medium-usage, or high-usage).
- 44 G) Rated Recovery Efficiency: Recovery efficiency in which the CWHP was certified.
- 45 H) User Interface: A means for a user to control the operation of the water heater, which may
46 be a remote and/or local user interface, such as a web-based portal, a mobile device
47 application, or an interface directly on the CWHP.
- 48 I) Utility Equivalent Communication Device: Self-contained or Personal Computer (PC)-
49 based device or devices capable of communicating with the CWHP and simulating
50 signals sent from a utility. The utility equivalent communication device or devices will be
51 controlled by the technician during the conduct of this test method, allowing the
52 technician to execute and deliver the DR requests and queries and receive necessary
53 feedback from the CWHP.
- 54 J) Acronyms:
- 55 1) ACM: Appliance Communication Module
56 2) API: Application Programming Interface
57 3) CWHP: Connected Water Heating Product
58 4) DR: Demand Response
59 5) GPM: Gallons Per Minute
60 6) ICD: Interface Control Document
61 7) UECD: Utility Equivalent Communication Device

62 **4 TEST SETUP**

63 Unless otherwise specified, all test conditions, instrumentation, and installation requirements
64 shall be identical to sections 2, 3, and 4 of the DOE Test Procedure.

65 The instrumentation which measures water volume, mass, and/or flow rate may be installed
66 on either the inlet or outlet side of the water heater.

67 The data acquisition system shall be able to measure and record the internal tank temperature
68 at a rate of 1 measurement every 5 seconds.


69 For solar water heaters that use grid energy as a backup heat source, all solar energy
70 connections should be disabled. The solar water heater shall then be tested according to its
71 backup heat source (e.g., if backup heating is provided by electric elements then the solar
72 water heater shall be tested as an electric resistance water heater and if backup heating is
73 provided by a gas burner then the solar water heater shall be tested as a gas-fired water
74 heater).

75 **4.1 Connected Water Heater Product (CWHP) System Setup**

76 The ACM and UECD shall be set up in accordance with manufacturer instructions in the
77 open standard protocol, ICD, and/or API. The communication devices must be set up as
78 follows:

- 79 A) Establish the connection between the ACM and the UECD via wired or wireless
80 connection depending on the ACM's capability. If both a wired and wireless connection
81 are available, connection between the ACM and UECD shall be through the wireless
82 connection.
- 83 B) Ensure that the ACM is connected properly and can both receive and send data to the
84 UECD, in accordance with manufacturer instructions.


85 For CWHP designed to be used with a mixing valve (e.g., the CWHP raises the temperature
 86 of water in the tank above the temperature of the water after all thermostats are satisfied at
 87 the user setpoint under normal operation, as specified in section 5.2.2 of the DOE Test
 88 Procedure, and that do not have a self-contained mixing valve), a mixing valve shall be
 89 installed according to the water heater and mixing valve manufacturer's instructions and to
 90 Figure 1 or Figure 2. If permitted by the water heater and mixing valve manufacturer's
 91 instructions, the mixing valve and junction which supplies the cold water to the mixing valve
 92 may be installed where the elbows are located in the outlet and inlet water lines, respectively..
 93 If there are no installation instructions for the mixing valve in the water heater or mixing
 94 valve manufacturer's instructions, then the mixing valve shall be installed on the outlet water
 95 line, as shown in Figure 1 or Figure 2, and the cold water shall be supplied from the inlet
 96 water line where a junction is installed between the water heater and the location where the
 97 inlet water temperature is measured. The outlet temperature, liquid flow rate, and/or mass
 98 measuring instrumentation, if installed on the outlet side of the CWHP, shall be installed after
 99 the mixing valve.



100

101

Figure 1: Mixing Valve location on a CWHP with top inlet and outlet connections



102

103 **Figure 2:** Mixing Valve location on a CWHP with side inlet and outlet connections

104 **5 WATER HEATER PREPARATION**

105 This section does not need to be performed to complete the CWHP Initialization (section
 106 6.1), User Interface (section 6.2), Consumer Override (section 6.3), and Loss of Connectivity
 107 (section 6.4) tests.

108 Prior to the Load Shift (section 6.5.1) and Emergency Curtailment and Grid Emergency
 109 (section 6.5.2) tests, perform the procedures found in section 5.1 and 5.2 of the DOE Test
 110 Procedure. These include the operational mode selection, determination of storage tank
 111 volume, V_{st} , setting the outlet discharge temperature, power input determination, and a soak-
 112 in period.

113 When setting the outlet discharge temperature, first use the settings as shipped from the
 114 manufacturer. If the requirements in section 5.2.2 of the DOE Test Procedure are not met,
 115 then adjust the temperature controller and repeat the procedures for setting the outlet
 116 discharge temperature.

117 If the DOE Test Procedure was performed prior to this test method and electricity and/or
 118 fossil fuel supply have not been removed from the CWHP, then the soak-in period from
 119 section 5.2.4 of the DOE Test Procedure does not need to be conducted.

120 **6 DEMAND RESPONSE TESTS**

121 In sections 6.3 through 6.5 test instructions are provided in table form where each row is a
 122 distinct step. DR requests are sent with a start time and duration. Start times can be either
 123 “Immediately” (i.e., as soon as the request is received by the CWHP) or at a certain time after
 124 the request is received by the CWHP. Durations are stated as either “Maximum” or some
 125 other duration (e.g., 4 hours). For all tests except the Loss of Connectivity test in section 6.4,

126 a “Maximum” duration in the context of this test method means first, that the DR request
 127 does not end, and second, if the CWHP is incapable of receiving a DR request that does not
 128 end, then the DR request will last at least 4 hours.

129 **Note:** A commenter recommended that event durations should be specified as this is how the
 130 requests will typically be sent in the field. The commenter further stated that the 4-hour
 131 duration used in the Load Shift test described in section 6.5.1 is an appropriate duration. EPA
 132 and DOE have adjusted the General Curtailment duration in the Load Shift test to 4 hours and
 133 if not possible to send a duration without an end time. All other durations were left the same
 134 as a “Maximum” duration will ensure that the desired tank conditions have enough time
 135 occur, in particular the Load Up request is left at “Maximum” to ensure that the CWHP is
 136 fully heated when the General Curtailment period begins.

137 **6.1 CWHP Initialization**

138 Verify that the CWHP communicates using an open standard as defined in section 4.D.a of
 139 the ENERGY STAR Specification.

140 **6.2 User Interface**

141 Verify that the manufacturer literature supplied with the CWHP and/or ACM includes
 142 instructions for the user to override DR requests.

143 **6.3 Consumer Override**

144 The test steps described in Table 1 shall be performed for the General Curtailment request to
 145 verify the consumer override requirement of section 4.D.b of the ENERGY STAR
 146 Specification.

147 All communications between the UECD and CWHP must be logged. If any logged
 148 communications do not match the acceptable responses, then the CWHP fails.

149 **Table 1: Consumer Override Verification Test Steps**

Step	UECD	CWHP
1	Send a Return to Normal Operation request.	
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3	Send a General Curtailment request. Start Time = Immediately Duration = Maximum	The CWHP must acknowledge the request.
4	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”

Step	UECD	CWHP
5	Initiate consumer override either through the local or remote user interface.	
6	Send an Operational State query.	Acceptable responses include: “Idle Opted Out” or “Running Opted Out”
7	Send a General Curtailment request. Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
8	Send an Operational State query.	Acceptable responses include: “Idle Opted Out” or “Running Opted Out”
9	End consumer override either through the local or remote user interface.	
10	Send a General Curtailment request. Start Time = Shortest possible duration allowing for time to complete Step 11 Duration = Maximum	CWHP must acknowledge the request.
11	Initiate consumer override either through the local or remote user interface.	
12		Wait for Start Time from Step 10.
13	Send an Operational State query.	Acceptable responses include: “Idle Opted Out” or “Running Opted Out”
14	End consumer override either through the local or remote user interface.	
15	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”

150 **Note:** A commenter suggested testing that the Consumer Override expires after a set time
151 period. The Final Draft of version 4.0 of the ENERGY STAR Specification requires a
152 maximum override time of 72 hours, without a requirement that it can be adjusted to be
153 shorter (though manufacturers may provide this at their discretion). Given this, EPA and
154 DOE have determined that testing the expiration of the override, which would take 72 hours,
155 will unduly increase the test time and burden.

156 **6.4 Loss of Connectivity**

157 The test steps described in Table 2 shall be performed to verify the loss of connectivity
 158 requirement of section 4.D.c of the ENERGY STAR Specification.

159 If unable to automatically verify operational state when connectivity is removed, manually
 160 verify operational state on the local user interface.

161 All communications between the UECD and CWHP must be logged. If any logged
 162 communications do not match the acceptable responses, then the CWHP fails.

163 Determine the time at which the CWHP should know that it is experiencing a loss of
 164 connectivity by multiplying the number of polling intervals from section 4.D.c of the
 165 ENERGY STAR Specification by the polling interval, which is dependent on the CWHP, this
 166 time is used in steps 5 and 13 of Table 2.

167 **Table 2: Loss of Connectivity Verification Test Steps**

Step	UECD	CWHP
1	Send a Return to Normal Operation request.	
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3	For CWHP’s capable of receiving DR requests without a set duration or end time, send a General Curtailment request. Otherwise, skip to step 11. Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
4	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
5		Remove connectivity and wait for the criteria described in section 4.D.c of the ENERGY STAR Specification to occur.
6		Wait for the time specified in section 4.D.c.ii of the ENERGY STAR Specification.
7		Re-establish connectivity and allow unit to perform any connection operations.
8	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
9	Send a Return to Normal Operation request.	

Step	UECD	CWHP
10	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
11	For CWHP’s capable of receiving DR requests with a set duration or end time, send a General Curtailment request. Otherwise, end test. Start Time = Immediately Duration = 4 hours	The CWHP must acknowledge the request.
12	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
13		Remove connectivity and wait for the criteria described in section 4.D.c of the ENERGY STAR Specification to occur.
14		Re-establish connectivity and allow unit to perform any connection operations.
15	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
16	Send a Return to Normal Operation request.	
17	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”

168 **Note:** A commenter suggested adding further description of the time that the CWHP would
169 be expected to wait before performing the actions described in section 4.D.c of the ENERGY
170 STAR Specification when experiencing a loss of connectivity. DOE and EPA have added a
171 description of the how long to wait before the CWHP should determine that a loss of
172 connectivity has occurred. This time is calculated multiplying the number of polling events
173 required by section 4.D.c of the ENERGY STAR Specification (i.e., 5 consecutive missed
174 polls are required before a loss of connectivity is determined) and the polling interval which
175 can be set while setting up the CWHP for test (e.g., if the polling interval was set to 5 minutes
176 then the CWHP should know that a loss of connectivity event has occurred after 25 minutes),
177 this time is used in steps 5 and 13. After a loss of connectivity event has been determined, the
178 CWHP should operate as described in section 4.D.c of the ENERGY STAR Specification and
179 when processing a DR event without a set duration or end time the product should return to
180 normal operation within the time limit found in section 4.D.c.ii (i.e., 30 minutes). Therefore,
181 in step 6 the instruction is to wait for 30 minutes before moving on to the next step.

182 The ENERGY STAR Specification now explicitly states that if the CWHP is capable of
183 storing and operating with a time of use schedule, the unit may continue operating on that
184 schedule during a loss of connectivity event. DOE and EPA have determined not to add steps
185 to the loss of connectivity test to verify this option as it is very similar to the option allowing
186 the CWHP to complete a DR event as planned when the DR event has a set end time.

187 **6.5 Demand Response Requests and Responses**

188 This section verifies the DR Requests and Responses of the CWHP as required by section
189 4.D.e of the ENERGY STAR Specification.

190 All communications between the UECD and CWHP must be logged. If any logged
191 communications do not match the acceptable responses, then the CWHP fails.

192 Prior to the Load Shift (section 6.5.1) and Emergency Curtailment and Grid Emergency
193 (section 6.5.2) tests perform the water heater preparation procedures from section 5.

194 Table 3 uses the Rated Draw Pattern to provide the flow rate used during the Load Shift and
195 the Emergency Curtailment and Grid Emergency tests. The CWHP’s Rated Draw Pattern is
196 also used to determine the Load Shift Draw Pattern as described in section 3.

197 **Table 3: Flow Rate Used in the Load Shift and Emergency Curtailment and Grid**
198 **Emergency Tests**

Rated Draw Pattern	Flow Rate
Very-Small-Usage	1.0 gpm ± 0.1 gpm
Low-Usage	1.7 gpm ± 0.1 gpm
Medium-Usage	1.7 gpm ± 0.1 gpm
High-Usage	3.0 gpm ± 0.25 gpm

199 During the Load Shift and Emergency Curtailment and Grid Emergency tests described in
200 sections 6.5.1 and 6.5.2, respectively, instructions are given to allow the CWHP to settle. To
201 “settle” in this test method is to allow the CWHP to operate without drawing water or
202 recovering for an entire settling period after a cut-out. If a cut-in occurs before the end of the
203 settling period, then the recovery should be allowed to continue until cut-out, at which time
204 the settling period will begin again, and, if necessary, repeat until a full settling period is
205 performed. A settling period is defined as the greater of 10 minutes or when a maximum
206 mean tank temperature is observed as determined when the 60-second rolling average of
207 mean tank temperature measurements, taken every 5 seconds, drops 0.05 °F below the
208 previous 60-second rolling average.

209 **Note:** A commenter suggested adding the criteria found in the Air-Conditioning, Heating, &
210 Refrigeration Institute’s (AHRI) Operations Manual for the Residential Water Heaters
211 Certification Program for determining when the CWHP has reached a maximum mean tank
212 temperature during a test. The commenter also recommended that a minimum time length be
213 included to avoid triggering a compressor lock out which is used to protect the compressor
214 from short cycling. DOE and EPA have added the criteria from the AHRI Operations Manual
215 for determining when a maximum mean tank temperature is observed mid-test and
216 maintained the 10-minute period to avoid a compressor lock out.

217 **6.5.1 Load Shift**

218 The test steps described in Table 4 shall be performed to verify the requirements for the
219 General Curtailment and either the Basic or Advanced Load Up requests from section 4.D.e
220 of the ENERGY STAR Specification. The Load Shift test includes performing the Load Shift
221 Draw Pattern with the CWHP in the Normal Mode of Operation, a load up (either a Basic or
222 Advanced Load Up), and then performing the Load Shift Draw Pattern with the CWHP
223 operating under a General Curtailment request. Only one load up request is required (i.e., if

224 the Basic Load Up is tested then verification of the Advanced Load Up is not required, and
 225 vice versa). Several steps in Table 4 use the flow rate that is determined using Table 3.

226 Record the mean tank temperature and energy usage at the beginning of the test and every 5
 227 seconds afterward.

228 **Table 4: Load Shift Test Steps**

Step	UECD	CWHP
If verifying the Advanced Load Up request, first enable Advanced Load Up operation.		
1	Send a Return to Normal Operation request.	
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3	Send a Device Type query.	CWHP must respond with Device Type.
4		If CWHP is undergoing a recovery, wait until cut-out and allow the CWHP to settle. If a recovery is not occurring, draw off water at the flow rate as determined using Table 3 until a cut-in occurs. Wait until cut-out and allow CWHP to settle.
Verification of Normal Mode of Operation		
5*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
6		Perform the Load Shift Draw Pattern. If a recovery initiates during the first draw of the Load Shift Draw Pattern, record the volume drawn at the initiation of the recovery.
7		Wait until 4 hours from the start of step 5 have elapsed.
8*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
9		If a recovery is occurring, wait until cut-out and allow the CWHP to settle.

Step	UECD	CWHP
		If a recovery is not occurring, draw off water at the flow rate as determined using Table 3 until a cut-in occurs. Wait until cut-out and allow CWHP to settle.
10*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
Verification of the Basic Load Up or Advanced Load Up Request		
11		<p>If a recovery initiated in the first draw of step 6, skip to step 12.</p> <p>If a recovery did not initiate in the first draw of step 6, draw off water at the flow rate as determined using Table 3. Stop drawing water when a cut-in occurs and wait for the CWHP to settle after cut-out.</p>
12 [†]		<p>Draw off water at the flow rate as determined using Table 3. If a recovery initiated in the first draw of step 6, stop drawing water when 2 gallons less than the volume drawn in step 6 have been drawn. If a recovery did not initiate in the first draw of step 6, stop drawing water when 2 gallons less than the volume drawn in step 11 have been drawn. If a cut-in occurs at any time before step 14, wait for the CWHP to settle after cut-out, and restart this step. After a restart of this step (only when necessary) draw off 1 gallon less than the volume drawn immediately before cut-in during the previous iteration until a volume of water is drawn off and no cut-in occurs.</p>
13*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
14	<p>Send either a Basic Load Up or Advanced Load up request.</p> <p>Start Time = Immediately</p> <p>Duration = Maximum</p>	CWHP must acknowledge the request.

Step	UECD	CWHP
15*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
16		If a cut-in does not occur within 5 minutes of sending the Basic Load Up or Advanced Load Up request, then the CWHP fails.
17*	If there was a delayed cut-in as described in step 16, perform this step. Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
18	Send an Operational State query.	Acceptable responses include: "Running Heightened Grid"
19		Wait for the CWHP to settle after cut-out.
Verification of the General Curtailment Request		
20*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
21	Send a General Curtailment request. Start Time = Immediately Duration = 4 hours. If the CWHP cannot accommodate a request of 4 hours, then the duration will be set to the shortest time greater than 4 hours or to a duration which does not end.	CWHP must acknowledge the request.
22	Send an Operational State query.	Acceptable responses include: "Running Curtailed Grid" or "Idle Grid"
23		Perform the Load Shift Draw Pattern.
24		Wait until 4 hours from the start of step 20 have elapsed.
25*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.

Step	UECD	CWHP
26	Send a Return to Normal Operation request.	
27	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
28*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
29		Wait for the CWHP to settle after cut-out. If a recovery does not occur after 10 minutes, move on to the next step.
30*	Send Power/Demand, Current Available Energy Storage Capacity, and if possible, Current Total Energy Storage Capacity queries.	CWHP must respond to all queries.
<p>* Calculate the energy content of the stored hot water in the CWHP as described in section 7.1.1.1.</p> <p>† Step 12 is intended to force the CWHP to be in a completely depleted energy state to measure the maximum amount of energy that could be used when loading up the CWHP. While not being tested, if a load up request was sent when the CWHP was only partially depleted, the CWHP should still load up despite not being in a fully depleted energy state. The exact energy state at which the CWHP initiates a recovery when a load up request has been received is determined by the manufacturer.</p>		

229 Determine the total energy consumed during the normal operation, Basic Load Up or
230 Advanced Load Up, and General Curtailment events:

231 Q_{Normal} = total energy consumption, including auxiliary energy use, between the start of step 5
232 and the end of step 8, Btu (Wh).

233 $Q_{\text{Basic Load Up}}$ = if applicable, total energy consumption, including auxiliary energy use,
234 between step 13 and the end of step 20, Btu (Wh).

235 $Q_{\text{Advanced Load Up}}$ = if applicable, total energy consumption, including auxiliary energy use,
236 between step 13 and the end of step 20, Btu (Wh).

237 $Q_{\text{General Curtailment}}$ = total energy consumption, including auxiliary energy use, between the start
238 of step 20 and the end of step 25, Btu (Wh).

239 Q_{Reheat} = total energy consumption, including auxiliary energy use, between the start of step
240 25 to the end of step 30, Btu (Wh).

241 Verify that: $Q_{\text{Normal}} > Q_{\text{General Curtailment}}$

242 Verify that the maximum power draw or fossil-fuel supply measurement that occurred after
243 the Basic Load Up or Advanced Load Up request was sent in step 14 and at or before the
244 time limit described in step 16 is greater than the power draw or fossil-fuel supply measured
245 in step 5.

246 **6.5.2 Emergency Curtailment and Grid Emergency**

247 Perform the test steps described in Table 5 to verify the Emergency Curtailment and Grid
 248 Emergency requirements from section 4.D.e of the ENERGY STAR Specification.

249 For CWHP that use heat pump technology along with resistance elements, if the resistance
 250 elements turn on at any point during an Emergency Curtailment event, then the CWHP fails.
 251 For CWHP that use only resistance heating elements, if any element but the top element turn
 252 on at any point during an Emergency Curtailment event, then the CWHP fails. For all CWHP,
 253 if any energy is used to heat water during a Grid Emergency event, then the CWHP fails.

254 Record the energy usage at the beginning of the test and every 5 seconds afterward.
 255 Measurements of the outlet temperatures shall be made 5 seconds after the draw is initiated
 256 and at every subsequent 3-second interval throughout the duration of each draw. Use Table 3
 257 to determine the flow rate used in the Emergency Curtailment and Grid Emergency
 258 Verification Test.

259 **Table 5: Emergency Curtailment and Grid Emergency Verification Test Steps**

Step	UECD	CWHP
1	Send a Return to Normal Operation request.	
2	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
3		If CWHP is undergoing a recovery, wait for the CWHP to settle after cut-out.
4*	Send Power/Demand and Current Available Energy Storage Capacity queries.	CWHP must respond to all queries.
5	Send an Emergency Curtailment request Start Time = Immediately Duration = Maximum	CWHP must acknowledge the request.
6	Send an Operational State query.	Acceptable responses include: “Running Curtailed Grid” or “Idle Grid”
7		Draw off water at the flow rate as determined using Table 3. When the delivery temperature reaches 80 °F (26.7 °C) continue with the next step.
8	Send a Grid Emergency request Start Time = Immediately	CWHP must acknowledge the request.

Step	UECD	CWHP
	Duration = Maximum	
9*	Send Power/Demand and Current Available Energy Storage Capacity queries.	CWHP must respond to all queries.
10		Stop drawing water when delivery temperature drops below 60 °F (37.8 °C).
11	Send a Return to Normal Operation request.	
12	Send an Operational State query.	Acceptable responses include: “Idle Normal” or “Running Normal”
* Calculate the energy content of the stored hot water in the CWHP as described in section 6.6.3.		

260 If testing a CWHP that uses heat pump and electric resistance elements, verify through
261 electrical supply measurements that the elements do not turn on between steps 5 and 7.

262 Verify through electrical and/or fossil fuel supply measurements that energy was not used to
263 heat water between steps 8 and 10.

264 **6.6 DR Information and Messaging**

265 Sections 6.6.1 to 6.6.5 verify the appropriate responses required in section 4.D.d of the
266 ENERGY STAR Specification.

267 **6.6.1 Device Type**

268 Verify that the device type recorded in step 3 of the Load Shift test described in Table 4 of
269 section 6.5.1 is the correct device type.

270 **6.6.2 Operational State**

271 The Operational State messaging is verified in sections 6.3 through 6.5.

272 **6.6.3 Current Available Energy Storage Capacity**

273 Verify that a response is being received from the Current Available Energy Storage Capacity
274 queries at each of the indicated steps in Table 4 of section 6.5.1 for the Load Shift test (i.e.,
275 steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and 30) and Table 5 of section 6.5.2 for the Emergency
276 Curtailment and Grid Emergency test (i.e., steps 4 and 9).

277 **6.6.4 Current Total Energy Storage Capacity**

278 Verify that a response is being received from the Current Total Energy Storage Capacity
279 queries at each of the indicated steps in Table 4 of section 6.5.1 for the Load Shift test (i.e.,
280 steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and 30) and Table 5 of section 6.5.2 for the Emergency
281 Curtailment and Grid Emergency test (i.e., steps 4 and 9).

282 **6.6.5 Power/Demand (Instantaneous)**

283 Verify that a response is being received from the Power/Demand (Instantaneous) queries at
284 each of the indicated steps in Table 4 of section 6.5.1 for the Load Shift test (i.e., steps 5, 8,
285 10, 13, 15, 17, 20, 25, 28, and 30) and Table 5 of section 6.5.2 for the Emergency
286 Curtailment and Grid Emergency test (i.e., steps 4 and 9).

287 Verify that the Power/Demand (Instantaneous) CWHP responses in steps 5, 10, 13, 20, and
288 30 in the Load Shift test from section 6.5.1 and steps 4 and 9 for the Emergency Curtailment
289 and Grid Emergency test from section 6.5.2 were less than the CWHP responses in step 15
290 (or step 17, if performed).

291 **7 CALCULATIONS**

292 **7.1.1 Accuracy of Current Available Energy Storage Capacity**

293 *7.1.1.1 Energy Content of the Stored Water*

294 Calculate the energy content of the stored water in the CWHP at each of the indicated steps in
295 Table 4 of section 6.5.1 for the Load Shift test (i.e., steps 5, 8, 10, 13, 15, 17, 20, 25, 28 and
296 30).

297
$$E_{step} = V_{st} \rho C_p \bar{T}_{Step}$$

298 Where,

299 E_{Step} = stored energy content of the CWHP during a specific step, Btu (Wh).

300 V_{st} = stored volume of the CWHP as found in section 5, gal (L).

301 ρ = density of the stored water at \bar{T}_{Step} , lb/gal (kg/L).

302 C_p = specific heat of stored water at \bar{T}_{Step} , Btu/(lb °F) (kJ/(kg °C)).

303 \bar{T}_{Step} = mean tank temperature during a specific step, °F (°C).

304 *7.1.1.2 Energy Content of the Stored Water after Cut-out during Normal Operation*

305 Calculate the average energy content of the CWHP when the mean tank temperature reaches
306 the maximum mean tank temperature after cut-out during normal operation, $\bar{E}_{Setpoint}$, by
307 averaging the calculated energy content of the CWHP at steps 5 and 10 from the Load Shift
308 test in Table 4. If the Basic Load Up request was verified then also include the calculated
309 energy content at step 20 the calculation (i.e., average of 3 different energy content
310 measurements if the Basic Load Up request was verified or 2 different energy content
311 measurements if the Advanced Load Up request was verified).

312 *7.1.1.3 Current Available Energy Storage Capacity*

313 Calculate the Current Available Energy Storage Capacity at each of the indicated steps in
314 Table 4 of section 6.5.1 for the Load Shift test (i.e., steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and
315 30). Note, there are 10 Current Available Energy Storage Capacity values.

316
$$AE_{C,Step} = \frac{(\bar{E}_{Setpoint} - E_{Step})}{RE_{Rated}}$$

317 Where,

318 $AE_{C, Step}$ = calculated Current Available Energy Storage Capacity for a specific step, Btu
319 (Wh).

320 RE_{Rated} = rated recovery efficiency, %.

321 *7.1.1.4 Root-Mean-Square Difference (RMSD)*

322 Calculate the RMSD between the calculated Current Available Energy Storage Capacity and
323 the recorded Current Available Storage Energy Capacity values which were supplied by the
324 CWHP during the Load Shift test from section 6.5.1.

325
$$RMSD_{AE} = \sqrt{\frac{\sum(AE_{C,Step} - AE_{R,Step})^2}{N}}$$

326 Where,

327 $RMSD_{AE}$ = root-mean-square-difference between the calculated Current Available Energy
328 Storage Capacity and the recorded Current Available Energy Storage Capacity, Btu (Wh).

329 $AE_{R, Step}$ = recorded Current Available Energy Storage Capacity supplied by the CWHP for a
330 specific step, as stated in section 7.1.1.3, Btu (Wh).

331 N = number of times the Current Available Energy Storage Capacity is measured during the
332 Load Shift test (i.e., 10).

333 **7.1.2 Accuracy of Current Total Energy Storage Capacity**

334 These calculations are optional and only apply to CWHP capable of receiving and responding
335 to Current Total Energy Storage Capacity requests.

336 *7.1.2.1 Energy Content of the Stored Water at High Energy State*

337 Determine the maximum mean tank temperature recorded between steps 10 and 21 of the
338 Load Shift test found in Table 4 of section 6.5.1, \bar{T}_{High} , °F (°C).

339 Calculate the energy content of the stored water in the CWHP at the high energy state.

340
$$E_{High} = V_{st} \rho C_p \bar{T}_{High}$$

341 Where,

342 E_{High} = stored energy content of the CWHP at the high energy state, Btu (Wh).

343 V_{st} = stored volume of the CWHP as found in section 5, gal (L).

344 ρ = density of the stored water at \bar{T}_{Low} , lb/gal (kg/L).

345 C_p = specific heat of stored water at \bar{T}_{Low} , Btu/(lb °F) (kJ/(kg °C)).

346

347 7.1.2.2 Energy Content of the Stored Water at Low Energy State

348 Determine the minimum mean tank temperature recorded between steps 21 and 24 of the
349 Load Shift test found in Table 4 of section 6.5.1, \bar{T}_{Low} , °F (°C).

350 Calculate the energy content of the stored water in the CWHP at the low energy state.

$$351 \quad E_{Low} = V_{st} \rho C_p \bar{T}_{Low}$$

352 Where,

353 E_{Low} = stored energy content of the CWHP at the low energy state, Btu (Wh).

354 7.1.2.3 Current Total Energy Storage Capacity

355 Calculate the Current Total Energy Storage Capacity.

$$356 \quad TE_C = \frac{(E_{High} - E_{Low})}{RE_{Rated}}$$

357 Where,

358 TE_C = calculated Current Total Energy Storage Capacity, Btu (Wh).

359 RE_{Rated} = rated recovery efficiency, %.

360 7.1.2.4 Root-Mean-Square Difference (RMSD)

361 Calculate the RMSD between the calculated Current Total Energy Storage Capacity and the
362 recorded Current Total Storage Energy Capacity values which were supplied by the CWHP
363 during the Load Shift test from section 6.5.1 (i.e., steps 5, 8, 10, 13, 15, 17, 20, 25, 28, and
364 30). Note, there are 10 Current Total Energy Storage Capacity values.

$$365 \quad RMSD_{TE} = \sqrt{\frac{\sum (TE_C - TE_{R,Step})^2}{N}}$$

366 Where,

367 $RMSD_{TE}$ = root-mean-square-difference between the calculated Current Total Energy
368 Storage Capacity and the recorded Current Total Energy Storage Capacity, Btu (Wh).

369 $TE_{R,Step}$ = recorded Current Total Energy Storage Capacity supplied by the CWHP for a
370 specific step, Btu (Wh).

371 N = number of times the Current Total Energy Storage Capacity is measured during the Load
372 Shift test (i.e., 10).

373 **7.1.3 Load Shift**

374 If the Basic Load Up request was verified during the Load Shift test, verify that the CWHP
375 meets the requirements of a Basic Load Shift.

376
$$Q_{Basic\ Load\ Up} + (Q_{Normal} - Q_{General\ Curtailment}) \geq Basic\ Load\ Shift$$

377 Where,

378 Q_{Normal} = as defined in section 6.5.1.

379 $Q_{Basic\ Load\ Up}$ = as defined in section 6.5.1.

380 $Q_{General\ Curtailment}$ = as defined in section 6.5.1.

381 Basic Load Shift = as defined in section 4.D.d.i of the ENERGY STAR Specification.

382 If the Advanced Load Up request was verified during the Load Shift test, verify that the
383 CWHP meets the requirements of an Advanced Load Shift.

384
$$Q_{Advanced\ Load\ Up} + (Q_{Normal} - Q_{General\ Curtailment}) \geq Advanced\ Load\ Shift$$

385 $Q_{Advanced\ Load\ Up}$ = as defined in section 6.5.1.

386 Advanced Load Shift = as defined in section 4.D.d.ii of the ENERGY STAR Specification.

387 **8 REFERENCES**

388 A) 10 CFR Part 430, Subpart E, Appendix B. Uniform Test Method for Measuring the
389 Energy Consumption of Water Heaters (as of January 1, 2021).

390 B) ENERGY STAR Program Requirements Product Specification for Residential Water
391 Heaters Version 4.0 (Rev. Feb-2021).